HASSAN DIVISION.

The 24th March 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 18th April 1898, for restoring the Chikka Gandasi tank, Registered No. 57, Arsikere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Chikka Gandasi tank, Registered No. 57, Arsikere taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Hassan division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice-board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork to bund	C. yds.	17,642
Preparing and fixing new grade stones with bed slabs	Each.	55
Vis a Vis stones	Do	55
B. M. stones	Do	2
Register No. stone	Do	1
Gauge do	Do	1
Date do	Do	1
Turfing do	S. yds.	16,124
Rough stone work new jelly pitching	C. yds.	1,912
Do old	Do	739
Jelly wedging to crevices of old stone revetment	Do	311
Clearing jungle bund	Lump sum Rupees.	
Sluices—		
Examining and repairing sluice No. I	Lump sum Rupees.	
Do do No. II	Lump sum Rupees.	
Waste weirs—		
Waste weir left, 46′ length—		
Excavation	C. yds.	20
Burnt brick in surki mortar	C. ft.	366
Burnt stone slabs	S. ft.	94
Plastering with surki mortar	Sqrs.	2·31
Rough stone work new sujicut	C. yds.	150
Waste weir, right, 136 feet—		
Excavation	C. yds.	862
Burnt brick in surki mortar	C. ft.	1,504
Burnt stone slabs	S. ft.	392
Plastering with surki mortar	Sqrs.	2·31
Rough stone work sujicut	C. yds.	360
Supply—		
Repairing the feeder channel left	Lump sum Rupees.	
Do do right	Lump sum Rupees.	

A. S. NAGAVKAR, *Exec. Engineer.*

KOLAR DIVISION.

The 1st March 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 15th April 1898 inclusive, for re-constructing Commandant's quarters, Commissioned Officer's quarters and huts for Barr sepoys stationed at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.